Neubau Schulhaus Rotweg



SHORT DESCRIPTION

In parts four stories high, the project is situated atop a public parking garage.

THE PROJECT

The longitudinal side of the existing adjoining building was built on. These façade elements were also clad with closed formwork consisting of cover strips.

SERVICES IN DETAIL

- New wood façade
- New wood ceiling panels in parking garage

CHALLENGES

The slatted wood façade is hung from wooden brackets mounted to the building`s exterior walls.  This required special attention be paid to the building envelope`s vapor barrier.

FACTS

Location	Rotweg 11, Wädenswil , Switzerland

Status	completed
Construction volume (value of our services)	850,000 CHF
Start of construction	January 2016
Completion	December 2016
Building owner	Stadt Wädenswil, Immobilien
General management	Daniel Baumann
Construction management	Meletta Strebel Architekten AG
Construction management	Meletta Strebel Architekten AG

SERVICES

Timber construction

Modular construction

https://implenia.com/en/references/detail/ref/construction-of-the-new-rotweg-school-building/

Creation: 14.11.2026 14:26