GYBUS - Extension of the sports hall in Bussigny



SHORT DESCRIPTION

The design for the expansion of the sports hall in Bussigny envisages a new building comprising 23 classrooms, an auditorium with 300 seats and a comprehensive sports infrastructure, including a triple hall and two rooftop sports fields.

THE PROJECT

The project to extend the gymnasium in Bussigny envisages the construction of a new building comprising 15 multi-purpose classrooms, 8 specialist rooms, a 300-seat auditorium, a VD6-type triple sports hall and two outdoor sports fields on the roofs of the future building.

CHALLENGES

Installation of 30-metre-long beams, each weighing 44 tons, which form the load-bearing scaffolding and enable the integration of two floors of classrooms above the future sports hall.

This challenge, which was completed in November 2025, required the use of a 450-ton mobile crane to transport the prefabricated beams.

SUSTAINABILITY

The project will be built to the Minergie-P/ECO standard.

FURTHER INFORMATION

Image ©: Fehlmann Architectes, Morges

FACTS

Location	Rte de Sullens 65, Bussigny , Switzerland
Status	Under construction
Construction volume (value of our services)	29 M CHF
Start of construction	January 2025
Completion	December 2027
Project management	Patrimonium Asset Management SA Succursale de Crissier Chemin des Lentillières 15 1023 Crissier
Architect	Fehlmann Architectes, Morges
Civil engineer	Nicolas Fehlmann Ingénieurs Conseil, Morges

SUSTAINABILITY

MINERGIE P-ECO

Minergie P-ECO

SERVICES

New constructions

General/full-service contracting - public use

https://implenia.com/en/references/detail/ref/gybus-extension-du-gymnase-de-bussigny/

Creation: 18.11.2026 00:02