New research building Center for Community Medicine Greifswald



SHORT DESCRIPTION

Implenia is supplying perforated metal louvre façades for the new interdisciplinary center for health research at the University Medical Center Greifswald (UMG).

THE PROJECT

As an interdisciplinary center for health research, the "William B. Kannel Center for Community Medicine" will unite six previously independent departments at different locations under one roof in order to further advance epidemiology, prevention and healthcare research.

Initial work on the construction project, which is jointly funded by the federal and state governments, began in October 2022 and is scheduled for completion at the end of 2026. The research building will then offer space for 379 employees on a usable area of 7488^{m2} and enable the daily examination of up to 173 people.

Facts about the overall project:

- Start of construction: 2022
- Planned completion: 2026
- Converted space: around 55,000 m^3
- Costs: approx. € 65.7 million

SERVICES IN DETAIL

Implenia Fassadentechnik GmbH has been awarded the contract for the perforated metal louvre façade lot. The service includes:

- 2,900 m² motorized vertical louvres made of aluminium frames with perforated sheet infill consisting of 1,720 individual louvres
- 2,900 m² steel substructure
- Sun position-guided control for large slats

FURTHER INFORMATION

Visualization: © MHB GmbH, Rostock

FACTS

Location	Felix-Hausdorff-Straße 8, Greifswald , Germany
Status	Under construction
Construction volume (value of our services)	1.5 M EUR
Start of construction	March 2025
Completion	September 2025
Building owner	Land Mecklenburg-Vorpommern vertreten durch das Finanzministerium d.v.d. die Leitung des Staatlichen Bau- und Liegenschaftsamtes Greifswald
Architect	MHB GmbH, Rosa-Luxemburg-Straße 4, 18055 Rostock

SERVICES

Fassadentechnik